

Nairobi City County Assembly invites bids for renovation of **Mathare North Ward Office**. The invitation to quote is **restricted to prequalified suppliers of Nairobi County Assembly for the year 2018/2020 under category NCCASB/PQ/27B/2018-2020** (Provision of minor Engineering Works and Renovations)

REPUBLIC OF KENYA
REQUEST FOR QUOTATION
QUOTATION NUMBER NCCA/Q/45/03/2018/2019

COMPANY NAME AND ADDRESS:

.....
.....

Buyer's designation and address: **Nairobi City County Assembly**
Box 45844-00100 Nrb
Date.3/04/2019

You are invited to submit quotation on items listed below:

Notes:

- a) **THIS IS NOT AN ORDER.** Read the conditions and instructions on reverse before quoting
- b) This quotation submitted in a plain wax sealed envelope marked "Quotation No. **NCCA/Q/45/03/2018/2019** For supply of: AS SHOWN BELOW and address to reach the buyer or be placed in the quotation Tender Box not later than **12:30pm on 9th April, 2019**
- c) Your quotation should indicate final unit price which quotation should include all costs for delivery, discount, duty and sales tax
- d) Return all the original copy and retain the duplicate for your reference.

Please quote for the; provision for renovations of Lower Savannah Ward office as per the attached Bill of Quantity (BQ).

FOR OFFICIAL USE ONLY:

Opened by; (1)	Designation.....	Signature.....
(2)	Designation.....	Signature.....
(3)	Designation.....	Signature.....
	Date.....	Time.....
	Sellers signature and Stamp.....	
	Date.....	

CONDITIONS

1. The general conditions of contract with the Government of Kenya apply to this transaction. This form properly submitted constitutes the entire agreement.
2. The offer shall remain firm for 30 days from the closing date unless otherwise stipulated by the seller.
3. The buyer shall not be bound to accept the lowest or any other offer, and reserved the right to accept any offer in part unless the contrary is stipulated by the seller.
4. Samples of offer when required will be provided free, and if not destroyed during test will, upon request, be returned at the sellers' expenses.

INSTRUCTIONS

1. All entries must be typed or written in ink. Mistakes must not be erased but should be crossed and corrections be made and initiated by the person signing the quotation.
2. Quote on each item separately, and in units as specified.
3. This form must be signed by a competent person and preferably it should be rubber stamped.
4. Each quotation should be submitted separately in a sealed envelope with the Quotation Number endorsed on the outside.
5. If you do not wish to quote, please state the reason on this form and return it, otherwise your name may be deleted from the buyer's mailing list for the items listed hereon.

GPK(L)

		Qty	Unit	Rate	Amt (Kshs.)
<u>PROPOSED RENOVATIONS OF EXISTING WARD OFFICES FOR THE NAIROBI CITY COUNTY ASSEMBLY - MATHARE NORTH WARD</u>					
<u>BILL NO. 1</u>	<u>BUILDER'S WORK</u>				
<u>RE-ROOFING</u>					
<u>Demolitions (Provisional)</u>					
A	Carefully remove existing worn-out asbestos tiles including ridge and hip caps, rotten fascia/barge boards and gutters, brandering; load and cart away arising debris (Approximately area- 125 square metres)		item		
<u>Sawn celcured second grade cypress:-</u>					
B	75 x 50mm purlins (provisional)	125	lm		
<u>Roof covering</u>					
<u>Gauge 28 pre-painted IT4 profile sheets fixed to purlins (m/s) with and including weathered rust proof screw bolts 75mm long with plastic cap laid with 300mm side and 150mm end laps as supplied by "Mabati Rolling Mills" or other equal and approved and fixing to timber purlins</u>					
C	Sheet covering to pitched roof	125	sm		
D	Ridge cap fixed to match laid with 150mm end laps	12	lm		
<u>Wrot prime grade cypress</u>					
E	250 x 25mm fascia and barge board with one labour	34	lm		
<u>Rain water goods</u>					
F	28 gauge 125 x 100mm U-shaped pre-painted gutter fixed to steel roof structure (m/s) with and including approved brackets	24	lm		
G	Extra over ditto for 75mm diameter down pipe outlet	4	no		
H	Extra over gutters for stopped ends	4	no		
I	Make 75mm diameter hole in gutter	4	no		
Carried to collections					

		Qty	Unit	Rate	Amt (Kshs.)
	<u>26 gauge pre-painted mild steel sheet in:</u>				
A	75mm diameter down pipe fixed to wall with and including approved holderbats	12	lm		
B	Extra over ditto for swan neck	4	no		
C	Ditto horse shoe	4	no		
	<u>Prepare and apply one undercoat and two finishing coats of "Crown" or other equal and approved gloss oil paint on:</u>				
D	Surfaces of wood exceeding 200mm but not exceeding 300mm girth externally	34	lm		
	<u>FINISHES</u>				
	<u>NB:- M.C.A.'s OFFICES AND CORRIDOR ONLY</u>				
	<u>FLOOR FINISHES</u>				
E	Carefully hack existing worn floor screed including skirting; prepare the floor to receive new floor finish internally and externally, load and cart away arising debris (Approximately area- 34 square metres)		item		
	<u>Cement/Sand (1:3) in:</u>				
F	30mm thick screed prepared to receive ceramic floor tiles (m/s)	34	sm		
	<u>Approved non slip coloured ceramic floor tiles from an approved stockist</u>				
G	300 x 300 x 10mm thick floor tiles fixed with an approved adhesive on prepared screed (m/s)	34	sm		
H	100 x 10mm thick skirting with rounded top ditto	42	lm		
	Carried to collections				
	<u>WALL FINISHES</u>				

		Qty	Unit	Rate	Amt (Kshs.)
<u>Painting and decorating</u>					
<u>Thoroughly scrub down previously painted surfaces of all dust, prepare and apply three coats of "Crown" or other equal and approved gloss oil paint on:</u>					
A	Previously painted wall surfaces measured overall over all doors and windows surfaces; internally	118	sm		
B	Ditto; externally (entire office block)	110	sm		
<u>CEILING FINISHES</u>					
<u>NB:- M.C.A.'s OFFICES AND CORRIDOR ONLY</u>					
<u>Demolitions (Provisional)</u>					
C	Carefully remove existing worn-out celotex ceiling including rotten brandering; load and cart away arising debris (Approximately area- 34 square metres)		item		
<u>Sawn celcured second grade cypress:-</u>					
D	50 x 50mm brandering (provisional)	34	lm		
E	100 x 50mm plugged ditto	15	lm		
<u>Ceiling boards</u>					
F	13mm thick cellotex ceiling boards internally fixed with symmetrical V-jointed patterns to existing timber brandering	34	sm		
G	Extra over cellotex ceiling in 600 x 600mm access door including the necessary framework and hinges	2	no		
<u>Wrot celcured cypress in:</u>					
H	100 x 25mm moulded cornice with six labours	49	lm		
<u>Painting and decorating</u>					
I	Prime back of frame before fixing not exceeding 100mm girth	64	lm		
Carried to collections					
<u>Prepare and apply one undercoat and two finishing coats of plastic emulsion paint on:</u>					

		Qty	Unit	Rate	Amt (Kshs.)
A	General surfaces of cellotex ceiling boards	34	sm		
B	Timber surface 100 - 200mm girth	49	lm		
	<u>DOORS</u>				
	<u>Security grille door</u>				
C	Standard steel grille door overall size 900 x 2400mm high comprising 50 x 50 x 3mm RHS plugged frame all round; infilled with 25 x 50mm RHS as directed; the door to include all necessary approved ironmongery and accessories	2	no		
	<u>Painting</u>				
	Prepare and apply one undercoat and two finishing coats of				
	"Crown" or other equal and approved plastic gloss paint to:				
D	General metal grilles surfaces	9	sm		
	<u>WINDOWS</u>				
	<u>Glazing</u>				
E	5mm thick clear sheet glass glazed with putty to metal in panes exceeding 0.10 but not exceeding 0.50 square metres	1	sm		
	<u>Burglar proofing</u>				
F	20 x 20mm mild steel bars cut and welded together at 150mm centres both ways as directed including plugging into masonry or/ and concrete including the necessary framework all round	3	sm		
	<u>Painting</u>				
	Prepare and apply one undercoat and two finishing coats of plastic emulsion paint as "Crown Paints" or other equal and approved on:				
G	General steel grilles measured overall both sides	6	sm		
	Carried to collections				
	<u>Metal work</u>				

		Qty	Unit	Rate	Amt (Kshs.)
A	30mm diameter moulded wrought iron single curtain rail/rod and 25mm diameter x 2mm thick mild steel pipe for sheers; including 50mm diameter circular curtain and sheer hooks to both rods at 50mm centres; complete with basket end on either side of curtain rod; wrought iron as "Iron Art" or other equal and approved	3	lm		
	<u>Curtains/blinds</u>				
B	Supply and fix approved vertical screening curtains/blinds complete with all necessary opening and closing gears and accessories to window openings all to approval (Provisional)	4	sm		
	Carried to collections				
	<u>COLLECTION</u>				
	Brought forward from page CA/1				
	Brought forward from page CA/2				
	Brought forward from page CA/3				
	Brought forward from page CA/4				
	Brought down from above				
	<u>BILL NO. 1</u>				
	<u>BUILDER'S WORK</u>				
	<u>TOTAL CARRIED TO</u>				
	<u>GRAND SUMMARY</u>				

		Amt (Kshs.)
<u>BILL NO. 2</u>		
<u>PROVISIONAL SUMS</u>		
A	Allow a Sum of Fifty Thousands only (Kshs. 50,000/=) for Contract Administration	50,000.00
B	Allow a Provisional Sum of Kenya Shillings One Hundred and Fifty Thousands only (Kshs 150,000/=) for Electrical Installations (Re-connection, Re-wiring, conduiting and upgrading of existing electrical installation)	150,000.00
C	Provide a Provisional Sum of Kshs Fifty Thousands only (Kshs. 50,000/=) for Contingencies	50,000.00
<u>PROVISIONAL SUMS</u>		
<u>TOTAL CARRIED TO GRAND SUMMARY</u>		

<u>PROPOSED RENOVATIONS OF EXISTING WARD OFFICES FOR THE NAIROBI CITY COUNTY ASSEMBLY - MATHARE NORTH WARD</u>			Amt (Kshs.)
<u>RENOVATIONS OF EXISTING OFFICES</u>			
<u>GRAND SUMMARY</u>			
<u>ITEM</u>	<u>PARTICULARS</u>	<u>PAGE NO</u>	
1.	PRELIMINARIES	PP/10	
2.	BILL NO. 1 - BUILDER'S WORK	CA/5	
3.	BILL NO. 2 - PRIME COST AND PROVISIONAL SUMS	PC/1	
		SUB-TOTAL	
		<u>ADD:-</u>	
		16% V.A.T.	
GRAND TOTAL CARRIED TO FORM OF TENDER			
CONTRACTOR..... ADDRESS..... DATE..... SIGNATURE..... WITNESS – NAME..... ADDRESS..... DATE..... SIGNATURE.....			