

Nairobi City County Assembly invites bids for renovation of **Mountain View Ward Office**. The invitation to quote is **restricted to prequalified suppliers of Nairobi County Assembly for the year 2018/2020 under category NCCASB/PQ/27B/2018-2020** (Provision of minor Engineering Works and Renovations)

REPUBLIC OF KENYA
REQUEST FOR QUOTATION
QUOTATION NUMBER NCCA/Q/49/03/2018/2019

COMPANY NAME AND ADDRESS:

.....
.....

Buyer's designation and address: **Nairobi City County Assembly**
Box 45844-00100 Nrb
Date.3/04/2019

You are invited to submit quotation on items listed below:

Notes:

- a) **THIS IS NOT AN ORDER.** Read the conditions and instructions on reverse before quoting
- b) This quotation submitted in a plain wax sealed envelope marked "Quotation No. **NCCA/Q/49/03/2018/2019** For supply of: AS SHOWN BELOW and address to reach the buyer or be placed in the quotation Tender Box not later than **12:30pm on 9th April, 2019**
- c) Your quotation should indicate final unit price which quotation should include all costs for delivery, discount, duty and sales tax
- d) Return all the original copy and retain the duplicate for your reference.

Please quote for the; provision for renovations of Lower Savannah Ward office as per the attached Bill of Quantity (BQ).

FOR OFFICIAL USE ONLY:

Opened by; (1)	Designation.....	Signature.....
(2)	Designation.....	Signature.....
(3)	Designation.....	Signature.....
	Date.....	Time.....
	Sellers signature and Stamp.....	
	Date.....	

CONDITIONS

1. The general conditions of contract with the Government of Kenya apply to this transaction. This form properly submitted constitutes the entire agreement.
2. The offer shall remain firm for 30 days from the closing date unless otherwise stipulated by the seller.
3. The buyer shall not be bound to accept the lowest or any other offer, and reserved the right to accept any offer in part unless the contrary is stipulated by the seller.
4. Samples of offer when required will be provided free, and if not destroyed during test will, upon request, be returned at the sellers' expenses.

INSTRUCTIONS

1. All entries must be typed or written in ink. Mistakes must not be erased but should be crossed and corrections be made and initiated by the person signing the quotation.
2. Quote on each item separately, and in units as specified.
3. This form must be signed by a competent person and preferably it should be rubber stamped.
4. Each quotation should be submitted separately in a sealed envelope with the Quotation Number endorsed on the outside.
5. If you do not wish to quote, please state the reason on this form and return it, otherwise your name may be deleted from the buyer's mailing list for the items listed hereon.

GPK(L)

		Qty	Unit	Rate	Amt (KShs.)
<u>PROPOSED GENERAL RENOVATIONS OF MOUNTAIN VIEW WARD OFFICES</u>					
<u>GENERAL RENOVATION WORKS</u>					
<u>BILL NO. 1</u>	<u>BUILDER'S WORK</u>				
<u>WALL FINISHES</u>					
<u>Painting</u>					
<u>Thoroughly rub off previously painted surfaces of all dust, prepare and apply three coats as "Crown" or other equal and approved plastic emulsion paint on:</u>					
A	Previously painted walls surfaces measured overall doors and windows; internally	192	sm		
<u>Thoroughly rub off previously painted surfaces of all dust, prepare and apply three coats as "Crown" or other equal and approved quality external paint on:</u>					
B	Previously painted walls surfaces measured overall doors and windows; externally	11	sm		
<u>FLOOR FINISHES</u>					
<u>Cement/Sand (1:3) in:</u>					
C	30mm thick screed prepared to receive ceramic floor tiles (m/s)	69	sm		
<u>Approved non slip coloured ceramic floor tiles from an approved stockist</u>					
D	300 x 300 x 10mm thick floor tiles fixed with an approved adhesive on prepared screed (m/s)	69	sm		
E	100 x 10mm thick skirting with rounded top ditto	50	lm		
<u>CEILING FINISHES</u>					
<u>Demolitions (Provisional)</u>					
F	Carefully remove existing worn-out celotex ceiling including rotten brandering; load and cart away arising debris (Approximately area- 78 square metres)		item		
Carried to collections					

[illegible]

		Amt (Kshs.)
<u>BILL NO. 2</u>		
<u>PROVISIONAL SUMS</u>		
A	Allow a Sum of Fifty Thousands only (Kshs. 50,000/=) for Contract Administration	50,000.00
B	Allow a Provisional Sum of Kenya Shillings Fifty Thousands only (Kshs 50,000/=) for Electrical Installations (Re-wiring, conduiting and upgrading of existing electrical installation)	50,000.00
C	Provide a Provisional Sum of Kshs One Hundred and Fifty Thousands only (Kshs. 150,000/=) for Contingencies	150,000.00
<u>PROVISIONAL SUMS</u>		
<u>TOTAL CARRIED TO GRAND SUMMARY</u>		

PROPOSED GENERAL RENOVATIONS OF MOUNTAIN VIEW WARD OFFICES			Amt (Kshs.)
RENOVATIONS OF EXISTING OFFICES			
GRAND SUMMARY			
ITEM	PARTICULARS	PAGE NO	
1.	PRELIMINARIES	PP/10	
2.	BILL NO. 1 - BUILDER'S WORK	CA/2	
3.	BILL NO. 2 - PRIME COST AND PROVISIONAL SUMS	PC/1	
		SUB-TOTAL	
		<u>ADD:-</u>	
		16% V.A.T.	
GRAND TOTAL CARRIED TO FORM OF TENDER			
CONTRACTOR..... ADDRESS..... DATE..... SIGNATURE..... WITNESS – NAME..... ADDRESS..... DATE..... SIGNATURE.....			